

PRZEDMIAR ROBÓT

tabela Nr 4

Wykop - nowa konstrukcja drogi

Lokalizacja [km]	Projektowana niweleta [km]	P [m ²]	Pśr [m ²]	L [m]	V [m ³]
a	b	c	d	e	f
68+540,00	0+742,00	3,0069			
			3,2554	10,00	32,554
68+550,00	0+752,00	3,5038			
			4,0310	10,00	40,310
68+560,00	0+762,00	4,5582			
			5,0605	10,00	50,605
68+570,00	0+772,00	5,5628			
			6,0613	10,00	60,613
68+580,00	0+782,00	6,5597			
			6,9646	10,00	69,646
68+590,00	0+792,00	7,3695			
			6,5351	10,00	65,351
68+600,00	0+802,00	5,7006			
			5,2486	10,00	52,486
68+610,00	0+812,00	4,7965			
			4,2662	10,00	42,662
68+620,00	0+822,00	3,7358			
			3,4261	10,00	34,261
68+630,00	0+832,00	3,1163			
			3,0365	10,00	30,365
68+640,00	0+842,00	2,9566			
Suma:					478,853

Frezowanie = 100,00m x 5,50m x 0,10m = 55,00 m³

Suma pomniejszona o frezowanie = 423,85 m³

Suwałki, dnia 25.03.2015r.

Sporządził: