

*Tabela objętości robót ziemnych - nasypy - m.Hołody*

Pikietaż	Objętość naspów z gruntu kat. II (poza konstrukcją chodnika) - N				
1	2	3	4	5	6
Km+hm	powierzchnia m2	śred. pow. m2	odległość m	objętość m3	suma objęt. m3
0,0	0,300				
28,0	0,060	0,180	28,0	5,040	5,04
46,0	0,030	0,045	18,0	0,810	5,85
89,0	0,050	0,040	43,0	1,720	7,57
114,0	0,230	0,140	25,0	3,500	11,07
156,0	0,110	0,170	42,0	7,140	18,21
203,0	0,050	0,080	47,0	3,760	21,97
235,0	0,080	0,065	32,0	2,080	24,05
254,0	0,180	0,130	19,0	2,470	26,52
271,0	0,160	0,170	17,0	2,890	29,41
293,0	0,100	0,130	22,0	2,860	32,27
313,0	0,120	0,110	20,0	2,200	34,47
353,0	0,000	0,060	40,0	2,400	36,87
398,0	0,020	0,010	45,0	0,450	37,32
438,0	0,010	0,015	40,0	0,600	37,92
456,0	0,000	0,005	18,0	0,090	38,01
484,0	0,000	0,000	28,0	0,000	38,01
500,0	0,020	0,010	16,0	0,160	38,17
530,0	0,040	0,030	30,0	0,900	39,07
575,0	0,040	0,040	45,0	1,800	40,87
576,0	0,950	0,495	1,0	0,495	41,37
605,0	1,170	1,060	29,0	30,740	72,11
646,0	1,460	1,315	41,0	53,915	126,02
695,0	0,890	1,175	49,0	57,575	183,60
752,0	0,570	0,730	57,0	41,610	225,21
760,0	0,000	0,285	8,0	2,280	227,49
788,0	0,000	0,000	28,0	0,000	227,49
797,0	0,180	0,090	9,0	0,810	228,30
		0,320	39,0	12,480	

*Tabela objętości robót ziemnych - nasypy - m.Hołody*

836,0	0,460	0,305	26,0	7,930	240,78
862,0	0,150	0,115	28,0	3,220	248,71
890,0	0,080	0,065	20,0	1,300	251,93
910,0	0,050	0,060	30,0	1,800	253,23
940,0	0,070	0,110	35,0	3,850	255,03
975,0	0,150	0,105	18,0	1,890	258,88
993,0	0,060	0,120	35,0	4,200	260,77
1 028,0	0,180	0,100	27,0	2,700	264,97
1 055,0	0,020	0,025	30,0	0,750	267,67
1 085,0	0,030	0,040	47,0	1,880	268,42
1 132,0	0,050	0,035	31,0	1,085	270,30
1 163,0	0,020	0,025	25,0	0,625	271,38
1 188,0	0,030	0,055	29,0	1,595	272,01
1 217,0	0,080	0,015	1,0	0,015	273,60
1 218,0	0,000	0,000	24,0	0,000	273,62
1 242,0	0,000	0,080	1,0	0,080	273,62
1 243,0	0,160	0,610	50,0	30,500	273,70
1 293,0	1,220	0,135	41,0	5,535	304,20
1 334,0	0,110	0,665	58,0	38,570	309,73
1 392,0	0,110	0,065	58,0	3,770	348,30
1 450,0	0,020				<b>352,07</b>

Objętość podbudowy na zjazdach w ramach chodnika

szer. Zjazdów (suma) mb	szer. Chodnika z obrzeżami (m)	gr. Konstrukcji chodnika (m)	
270,5	1,66	0,24	<b>107,77</b>
(wg tabeli robót na zjazdach)			(m3)

Objętość nasypów (m3) **244,30**