

# PRZEDMIAR ROBÓT

załącznik nr 1

## Nasyp z gruntu kat. III-IV (chodnik)

Lokalizacja [km]	P [m <sup>2</sup> ]	Pśr [m <sup>2</sup> ]	L [m]	V [m <sup>3</sup> ]
a	c	d	e	f
115+216,00	0,0000			
115+230,00	1,0205	0,5103	14,00	7,14
115+250,00	0,8276	0,9241	20,00	18,48
115+270,00	0,8371	0,8324	20,00	16,65
115+290,00	0,6908	0,7640	20,00	15,28
115+310,00	1,4303	1,0606	20,00	21,21
115+330,00	3,1352	2,2828	20,00	45,66
115+350,00	3,3758	3,2555	20,00	65,11
115+370,00	3,2172	3,2965	20,00	65,93
115+390,00	2,7749	2,9961	20,00	59,92
115+410,00	1,0131	1,8940	20,00	37,88
115+430,00	1,6367	1,3249	20,00	26,50
115+450,00	0,9453	1,2910	20,00	25,82
115+470,00	1,6811	1,3132	20,00	26,26
115+490,00	0,9379	1,3095	20,00	26,19
115+510,00	3,0750	2,0065	20,00	40,13
115+530,00	2,4684	2,7717	20,00	55,43
115+550,00	2,8567	2,6626	20,00	53,25
115+570,00	1,5617	2,2092	20,00	44,18
115+590,00	2,0338	1,7978	20,00	35,96
115+610,00	2,4568	2,2453	20,00	44,91
115+630,00	3,3002	2,8785	20,00	57,57
115+650,00	2,0455	2,6729	20,00	53,46
115+680,00	1,1757	1,6106	30,00	48,32
115+698,00	1,6205	1,3981	18,00	25,17
Suma:				<b>916,41</b>

Suwałki, dn. 26.05.2010r.

Sporządził: