

tabela robót na zjazdach od km 38+200 do km 45+000

lp	km	strona		podbudowa z ruszywa naturalnego gr 25cm [m ²]	nawierzchnia [m2]	
		L	P		bitum. 5cm	żwir 20cm
1	38+271		P			37
2	38+276	L				37
3	38+798	L		41	37	
4	39+348		P			37
5	39+348	L				37
6	40+447		P			37
7	40+447	L				37
8	40+290		P			37
9	40+293	L				37
10	40+502		P			37
11	40+502	L				37
12	41+025		P			37
13	41+040	L				37
14	42+147		P			37
15	42+562	L		100	95	
16	42+622	L				37
17	42+662	L		100	95	
18	43+075	L				37
19	43+208		P			37
20	43+208	L				37
21	43+476	L				37
22	43+763	L				37
23	43+763		P			37
24	43+932	L		42	40	
25	44+217		P			37
26	44+242	L				37
27	44+243		P			37
28	44+530	L				37
29	44+586	L				37
30	44+801		P	39	37	
31	44+870		P	39	37	
	razem			360,2	341	925